

Page 1 of 10

APPLICATION

NYU Langone Health

PURPOSE

To protect personnel who enter confined spaces and permit-required confined spaces (PRCSs)

To comply with the Occupational Safety and Health Administration (OSHA) standards on confined space entry (General Industry: 29 CFR 1910.146 and Construction: 29 CFR 1926 Subpart AA)

POLICY

1.0 **Application**

NYU Langone Health (NYULH) refers to the NYU Langone Health System, NYU Langone Hospitals, NYU Grossman School of Medicine, NYU Long Island School of Medicine, the Family Health Centers at NYU Langone, and all entities controlled by any of them.

This policy applies to:

- All indoor and outdoor areas of all NYULH owned and leased facilities
- All employees, contractors, and consultants of NYULH

The primary departments and divisions impacted by the program are:

- Facilities (Facilities Management, Facilities Operations, and Engineering)
- Real Estate
- RED+F Design and Construction
- Environmental Services
- Contractors and subcontractors

2.0 **Definitions**

Attendant refers to an individual stationed outside a PRCS who assesses the status of authorized entrants and performs the duties specified in the applicable OSHA PRCS standard.

Authorized entrant refers to an individual who is authorized to enter a PRCS.

Competent person means one who is capable of identifying existing and predictable hazards in the surroundings or working conditions which are unsanitary, hazardous, or



dangerous to personnel, and who has the authorization to take prompt corrective measures to eliminate them.

Confined space means a space that:

- Is large enough and so configured that a person can bodily enter and perform assigned work; and
- Has limited or restricted means for entry or exit (e.g., tanks, vessels, boilers, pits, vaults, manholes, sewers, drains, water mains, ceiling plenums, ductwork); and
- Is not designed for continuous occupancy.

Controlling contractor refers to the employer that has overall responsibility for construction at the worksite (e.g., prime contractor, general contractor, or construction manager).

Entry supervisor refers to the person who is responsible for determining if acceptable entry conditions are present at a PRCS where entry is planned, for authorizing entry, overseeing entry operations, and for terminating entry as required by the applicable OSHA PRCS standard. On construction projects, the entry supervisor must meet OSHA's definition of a qualified person (see below).

Permit refers to NYULH's PRCS permit (see Appendix A) completed in accordance with Appendix B, or another permit authorized by Environmental Health and Safety (EH&S).

Permit-required confined space (PRCS) has one or more of the following characteristics:

- Contains or may contain a hazardous atmosphere
- Contains a material that may engulf an entrant
- Has an internal configuration that can trap or asphyxiate an entrant
- Has any other serious health or safety hazard

Program means the employer's overall program for controlling, and where appropriate, protecting employees from, PRCS hazards, and for managing employee entry into PRCSs.

Qualified person means one who, by possession of a recognized degree, certificate or professional standing, or by extensive knowledge, training and experience, has successfully demonstrated the ability to solve or resolve problems relating to the subject matter, the work, or the project.



Page 3 of 10

3.0 **Responsibilities**

- 3.1 Environmental Health and Safety (EH&S) is responsible for:
 - Developing the PRCS Entry Program (the Program) and collaborating with others to implement and maintain it.
 - Providing confined space awareness training to relevant groups, including Facilities, Real Estate, RED+F Design and Construction, and Environmental Services.
 - Functioning as a consultant on an as needed basis for confined space and PRCS entry issues.
 - Maintaining a list of qualified, approved consultants who can provide confined space training and assist staff with oversight of PRCS work including atmospheric testing.
 - Evaluating the effectiveness of the Program and recommending changes as needed.
- 3.2 **Facilities and Real Estate** are responsible for:
 - Managing the Program and the permitting process in facilities they maintain.
 - Ensuring that all PRCSs are identified and included in the Program.
- 3.3 The Vice Presidents and Directors of Facilities, Real Estate and RED+F Design and Construction are responsible for compliance within their departments and divisions. Their responsibilities include, but are not limited to:
 - Implementing the Program within their departments and divisions.
 - Ensuring all requirements of this policy are followed.
 - Ensuring all PRCS work is identified and included in the Program.
 - Ensuring all personnel who participate in confined space and PRCS work receive the training outlined in Sections 7 and 8 of this policy prior to assignment.
 - Ensuring that employees have the required safety equipment.
 - Ensuring contractors comply with this policy.
- 3.4 **Managers and forepersons** are responsible for:
 - Implementing and maintaining the Program within their work groups.



- Notifying EH&S (or the Sr. Director of Engineering at NYU Langone Hospital-Long Island (NYULH-LI)) of PRCS work one (1) week in advance for planned work and immediately for emergencies.
- Ensuring all personnel who participate in confined space and PRCS work have the training outlined in Sections 7 and 8 of this policy prior to assignment.
- Submitting a Job Safety Analysis (JSA) (a step by step plan for completing PRCS work, which lists the hazards associated with the work and the plan for addressing them) to EH&S, or the Sr. Director of NYULH-LI Engineering, or an authorized consultant, as applicable, for review. The JSA shall also address emergency rescue procedures (e.g. non-entry rescue, qualified rescue vendor).
- Ensuring their employees have the required safety equipment.
- Ensuring shutdown and lockout/tagout of necessary utilities.
- Ensuring contractors comply with this policy (e.g., submit a written PRCS program, training records, and JSA for review, employ necessary safety equipment).
- 3.5 **Project managers (PMs)** (e.g., design, construction, renovation, operations, and maintenance) and **Tenant Coordinators (TCs)** are responsible for:
 - Implementing and maintaining the Program at their facility or on their project.
 - Ensuring employees and contractors comply with this policy by:
 - Incorporating the requirements of the policy into the specifications for the work.
 - Informing contractors about the requirements of this policy during the bidding process.
 - Notifying EH&S (or the Sr. Director of Engineering at NYULH-LI) of PRCS work one (1) week in advance.
 - Submitting contractor's training documents, written PRCS program, and JSA to EH&S, or the Sr. Director of NYULH-LI Engineering, or an authorized consultant, as applicable, for review.
 - Coordinate the shutdown and lockout/tagout of necessary utilities.
 - During the design or redesign phase, seeking feasible solutions to eliminate PRCS hazards and entry (e.g., by providing unrestricted access and egress, designing test holes).



3.6 **Controlling contractors and subcontractors** are responsible for:

- Complying with all provisions of the OSHA Confined Spaces in Construction standard and requirements of this policy.
- Informing managers, PMs and TCs about the existence, creation, and modification of PRCSs during construction or renovation at least one (1) week in advance.
- Preventing unauthorized entry to PRCSs by posting warning signs consistent with Section 4.0 of this Policy and securing PRCS entry by locked cover, hatch, or other effective means.
- Obtaining copies of PRCS training documents for the entry supervisor, attendant, and authorized entrants and submitting them to the PM or TC. Ensuring that the entry supervisor meets OSHA's definition of a qualified person.
- Obtaining, reviewing and submitting the contractor's written PRCS program and JSA to the PM or TC. The JSA shall also address emergency rescue procedures (e.g. non-entry rescue, qualified rescue vendor).

3.7 Workers who participate in confined space and PRCS work are responsible for:

- Attending the training outlined in Section 8 of this policy prior to assignment.
- Requesting a Permit prior to entering any PRCS.
- Following the requirements of the Permit.
- Immediately notifying their supervisors of any pertinent problems.

4.0 **PRCS identification and signage**

4.1 Facilities and Real Estate identify all PRCSs in their facilities, and install signs on or stencils each space reading DANGER - PERMIT-REQUIRED CONFINED SPACE - DO NOT ENTER. A list of PRCSs in owned spaces is included as Appendix C.

5.0 **PRCS entry procedures**

5.1 The foreman, manager, PM or TC shall contact EH&S, or the Sr. Director of Engineering at NYULH-LI, or an authorized consultant one (1) week prior to scheduling work in a PRCS and provide a brief scope of work to be performed.



For emergency work, they shall contact EH&S, the Sr. Director of NYULH-LI Engineering or designee, or the consultant immediately.

- 5.2 Prior to work in a PRCS, the entry supervisor shall evaluate all potential hazards present in, and introduced into, the space, and implement appropriate controls.
- 5.3 Prior to work in a PRCS, personnel shall obtain a Permit (see Appendix A) from Facilities or Real Estate and complete it in accordance with Appendix B.
 - For in-house work, the employee's manager or foreperson shall function as the entry supervisor. The entry supervisor shall:
 - Prepare the work area for PRCS entry.
 - Complete entry permit.
 - Sign and authorize the work.
 - For work by contractors, the manager, PM or TC shall initiate the Permit.
 - The PM shall coordinate the work with the Facilities manager, property owner, or TC.
 - The contractor entering the PRCS shall designate the entry supervisor. The entry supervisor shall:
 - Complete and sign the Permit in the presence of the manager or controlling contractor's competent person following the steps listed above (under in-house work).
 - Ensure the roles and duties of the entry team are made clear prior to the entry.
 - Report to the controlling contractor's competent person during the entry and following the conclusion of the entry.
- 5.4 A completed and authorized Permit shall be valid until:
 - The end of the workers' shift or the work is completed, whichever comes first; or
 - There is an emergency involving or affecting the work area.
- 5.5 The signed Permit shall be posted in the work area until the Permit is no longer valid or the work is completed.



- 5.6 During the entry, the entry supervisor shall stay in radio contact with the attendant. The attendant shall call the entry supervisor when the work is complete or in case of an emergency.
 - In the case of an emergency, the entry supervisor shall:
 - Contact 911 and indicate that PRCS rescue is required
 - Contact Telecommunications at 33-911 or 212-263-911
- 5.7 The entry supervisor, and foreman or controlling contractor's competent person shall inspect the work area periodically during the work to ensure that the conditions of the Permit are maintained.
- 5.8 The manager or controlling contractor's competent person shall debrief the employees or contractor who completed the work regarding any challenges encountered during the work, and communicate identified issues to EH&S or the Sr. Director of NYULH-LI Engineering, as applicable.
- 5.9 When the work is completed and the authorized entrants have left the PRCS, all systems shall be returned to their original condition. The Facilities manager or TC shall check the work area and authorize systems to be put back into service.
- 5.10 The NYULH Permit shall be closed out or cancelled by the entry supervisor by filling out Section 10 of the Permit.
- 5.11 The foreman or controlling contractor's competent person shall return the Permit to the Facilities office or the TC.
 - For in-house work, the foreman returns the Permit to the Facilities office.
 - For work done by contractors, the controlling contractor's competent person returns the Permit to Facilities or the TC.
- 5.12 Facilities managers or Real Estate shall maintain Permits for completed work for at least one year.

6.0 **Construction notifications**

- 6.1 Prior to construction activities, the PM shall notify EH&S or the NYULH-LI Sr. Director of Engineering, as applicable, of any potential confined space or PRCS work within their site.
- 6.2 During construction activities, the controlling contractor's competent person shall notify the PM of the creation or modification of any PRCS (e.g., temporary



Page 8 of 10

crawlspaces) and the PM shall notify EH&S or the NYULH-LI Sr. Director of Engineering, as applicable.

7.0 **Confined space awareness training**

- 7.1 Managers and the controlling contractor's competent person shall ensure that all personnel who participate in confined space work have confined space awareness training.
 - Training for employees shall be conducted by Environmental Health and Safety or provided through completion of NYULH's eLearning module.

8.0 **PRCS Training**

- 8.1 Managers and the controlling contractor's competent person shall ensure that all personnel who participate in PRCS work have 8-hour confined space Entrant/Attendant/Supervisor training prior to assignment. The entry supervisor, attendant and authorized entrants shall be familiar with the:
 - Requirements of this policy
 - Proper preparation of a PRCS for entry
 - Potential hazards encountered in a PRCS
 - Use of proper safety equipment and PPE
 - The duties and responsibilities of each member of the PRCS entry team
 - Emergency procedures (e.g., incident and injury protocols)
- 8.2 Training shall be conducted:
 - Before a worker is first assigned to PRCS entry
 - Before a worker is assigned new PRCS tasks
 - Whenever there is a change in procedures or new hazards are introduced
 - Whenever there are deviations from the requirements of the policy, or there are inadequacies in a worker's knowledge or use of these procedures
- 8.3 Each department/division shall maintain training records for its employees.
 - Records shall include the dates of training, subjects covered, names of employees trained, and name and signature of the trainer
 - Records shall be maintained for 1 year past the last day of employment
 - Copies of records shall be provided to EH&S upon request



9.0 **Program evaluation**

EH&S shall conduct an annual evaluation of the Program as part of the annual evaluation of NYULH's Environmental Safety Management Plan.

Appendix A	NYULH Confined Space Entry Permit			
Appendix B	Instructions for Preparing a PRCS for Entry and Completing the Permit			
Appendix C	List of Permit-Required Confined Spaces in Facilities Owned by NYU Langone			

Issue date	03/2021		
Replaces	12/2019		
Reviewed by	E. Cintron, Real Estate		
_	R. Cohen, Facilities Operations		
	N. Ejaz, NYULH-B Safety Officer		
	S. Haney, Environmental Health and Safety		
	A. John, Environmental Services		
	B. Kenny, NYULH-LI, Engineering		
	D. Resnick, Design and Construction		
	D. Rubbo, NYULOH Engineering		
	NYU Langone Hospital Environment of Care (EOC) Committee		
	NYU Langone Orthopedic Hospital EOC Committee		
	NYU Langone Hospital – Brooklyn EOC Committee		
	NYU Langone Hospital – Long Island EOC Committee		
	Family Health Centers at NYU Langone EOC Committee		

Summary of Revisions

Revision date	Section	Changes		
March 2021	Throughout	Changes NYU Winthrop to NYU Langone Hospital-Long Island		
November 2019	Throughout	Change "confined space" to "PRCS" for clarity. Adds		
		responsibilities of NYUWH Sr. Director of Engineering.		
	1.0	Incorporates Winthrop and NYU Long Island School of Medicine		
	1.0 and 3.1	Adds Environmental Services		
	5.3	Reorganized, for clarity		
	7.0	Adds awareness training		
	Reviewed by	Adds review by NYU Winthrop Hospital		
November 2017	Throughout	Updates logo and organizational references		
	3.4 and 3.5	Updates responsibilities		
	Appendix C	Updates PRCS locations at NYULH-B, Kimmel, and Science		
February 2017	Application	Changes NYULMC to NYU Langone		
	1.0	Defines NYU Langone		



Page 10 of 10

2.0	Updates definitions
	Adds definitions for competent person and controlling contractor
3.4, 3.5, 3.6	Updates responsibilities for forepersons, PMs, and controlling
	contractors
4.0 and 5.0	Adds Lutheran
	Updates confined space entry procedures
7.0	Updates training requirements
Review by	Adds review by Lutheran Safety Officer, and HJD, Lutheran, and
	Lutheran Family Health Centers EOC Committees
Summary of	Adds Summary of Revisions
Revisions	
Appendix A-	Updates appendices
C	

NYULH Confined Space Entry Permit

SECTION 1: H	SECTION 1: Entry Permit (valid for 8 hours only)												
Date: Start time:			e: AM/PM I				Expi	ration time:		AM/PM			
Building:					Location:								
Job supervisor	Job supervisor:				Equipment to be worked on:								
Reason for Entry:													
Location of ne	Location of nearest fire alarm pull station: Nearest telephone:												
Rescue proced	ures: Attempt n	on-entry res	cue. C	all 91	11 and alert	dispa	atcher o	of a con	fined	l space emer	gency. T	hen call NYUI	H
telecommunicat	tions at 212-263	-3911 (3391	1).										
SECTION 2: F	SECTION 2: Permit Space Hazards SECTION 3: Hazard Elimination												
	n Deficient/Enri				Contac	et Irri	tant			Lockou	t/Tagou	t	
Flamm	able Gases/Vap	ors/Liquids			Enguli	fment				Purge/C	Clean		
	ustible Dust				Noise					Blank			
	Gases/Vapors (S	, <u>,</u>			Hot W	'ork				Ventila	tion		
	cal/Mechanical	Hazard			Heat/C	Cold S	Stress			Barrier	5		
	cal Hazard			Oth	ner:					her:			
SECTION 4: F							SEC			ifety Equipn	nent		
	al Splash	Ir	npervio	ous S	Suit			Full	Body	y Harness	_	Safety Line	9
Goggles													
	ous Boots		ard hat					Esca	_	ottle		GFCI	
	Protection		<u> </u>	ory I	Protection			Tripo				Radios	
Coveral	ls		loves							tage Tools		Fire Extin	ıg.
Other:		Other:						·····		n Proof Equi			
Other:		Other:								Monitor for			
	Atmospheric M	onitoring (t	-		-	ry an	id con	tinuous	ly w			30 mins)	
Model:				ial #:					Monitor (Print):				
Field Check:	PassF	ail			tion Due: _					Monitor (Sign):		<u> </u>
D			Initia			D				D	-	D. L	-
Parameter	Acceptable C		Resu	lts	Time	Res	sults	Tim	e	Results	Time	Results	Time
Oxygen LEL	>19.5% and < <10% LEL	23.5%			-								-
		7											-
H ₂ S CO	Contact EH&S												-
VOCs	Contact EH&S												
Other:	Contact Ends)											
Other:													
	Communication	Drogoduro	o Dotu		Entront(s)	and	Attond	lant			L		
Voice/V		rioceuure	Rad		Entrant(8)		Attenu	Other:					
SECTION 8: F		RINT NAM					(\$1(GN NAN	AE)				
Entry Supervis	,		112)				010)		112)				
Attendant	501												
Entrant													
Entrant													
	SECTION 9: Entry Authorization												
All training requirements have been met \Box (Permit cannot be authorized if this box is unchecked)													
I have reviewed the work authorized by this permit and the information contained here-in. Written instructions and safety procedures													
have been received and are understood. Entry cannot be authorized if any questions have been answered "No." This permit is not valid													
unless all appropriate items are completed.													
Entry Superviso	-								Da	te:		Time:	
Manager's sign	-								Da			Time:	
SECTION 10:		ntion											
Reason for Can	-		Vork C	omp	lete		F	Emergen	cv		Other:		
Entry Superviso		· _ · _ ·							Date: Time:				
					Da	te:		Time:					
5 9	Tanager's signature.												

SECTION 1

When it is determined that a permit-required confined space (PRCS) must be entered to perform work, the entry supervisor will complete Section 1 of the Permit. The REASON FOR ENTRY section should state the work to be completed in the PRCS (e.g., welding).

SECTION 2

Permit Space Hazards

The entry supervisor will examine the PRCS for potential hazards and will complete Section 2 of the Permit. EH&S, or the NYULH-LI Sr. Director of Engineering, or an authorized consultant shall be contacted for assistance in identifying potential hazards.

SECTION 3

Hazard Elimination

The entry supervisor, along with other applicable personnel, shall eliminate the feasible hazards and complete Section 3 of the Permit. Examples of hazard elimination include:

Lockout/Tagout

OSHA-compliant lockout/tagout procedures should be followed. If there is no equipment requiring lockout/tagout N/A should be checked.

Equipment purging and cleaning

The PRCS should be purged of its contents and cleaned if necessary to protect workers who will enter it. If the PRCS contained chemicals, or chemicals are used to clean it, EH&S or NYULH-LI Hospitality Services, as applicable, should be contacted for disposal of these chemicals, cleaning solution, and any rinse water that may contain chemical contaminants. If no cleaning is necessary, N/A should be checked. If the equipment cannot be cleaned, EH&S or the NYULH-LI Sr. Director of Engineering, as applicable, should be contacted for any special procedures that may be necessary.

All lines disconnected, blanked or plugged

All pipelines that are connected to a PRCS must be disconnected, blanked or plugged so that no contaminants will enter the PRCS during entry. Where the pipeline cannot be completely isolated (e.g., sewers), it shall be isolated to the extent possible to reduce contaminants and sudden flooding.

Ventilation

Continuous forced air ventilation is necessary where the atmosphere in a PRCS does not meet acceptable levels for oxygen and air contaminants. All ventilation equipment must be explosion proof and draw in fresh air at standard temperature and pressure. Where forced air ventilation does not maintain an acceptable atmosphere, the use of air purifying or supplied air respirators is necessary, which requires involvement of EH&S or an authorized consultant.

Barriers

A barrier shall be installed to prevent anyone from falling into the PRCS and to keep pedestrians away from it.

SECTION 4 and 5

Personal Protective and Safety Equipment

Based on an assessment of the hazards in the PRCS, workers must be supplied with the necessary personal protective and safety equipment.

Lighting should be provided to illuminate the work area inside the PRCS. All lighting must be explosion proof.

The attendant and entrant(s) should be provided with radios to communicate during the operation.

Other Equipment that may be necessary

The entry supervisor should check on the Permit any other equipment that the workers may need to enter the PRCS. This may include, but is not limited to, the equipment listed in Sections 4 and 5 of the Permit

SECTION 6

Atmospheric Monitoring

Personnel shall use a recently calibrated continuous air monitor to do a pre-entry atmospheric check in the PRCS for oxygen deficiency, lower explosive limit (L.E.L.), carbon monoxide (CO) and hydrogen sulfide (H₂S). The percent oxygen should be 19.5-23.5%. The L.E.L. should be less than 10%. For CO, H₂S, and other air contaminants, contact EH&S or the authorized consultant to determine the levels not to be exceeded. Additional tests for toxicity shall be done for chemical present within, or introduced into the PRCS. The person conducting the test will sign next to the results for the pre-entry

atmospheric checks when the levels are within the prescribed limits. Atmospheric monitoring shall be conducted continuously during entry and recorded every 30 minutes during the entry. If any of these test results are not in the prescribed range, forced fresh air ventilation into the PRCS shall be used until the required levels are met.

SECTION 7

Communication Procedures

The entry supervisor should determine the most effective way for the authorized entrant(s) and the attendant to stay in contact. This may include, but is not limited to, voice or visual communication or two-way radio communication.

Cell phones shall not be used for communication within a PRCS.

SECTION 8

Personnel

The entry supervisor will list the authorized entrant(s) that will enter the PRCS. The entry supervisor will also write the name of the attendant that will be monitoring the entrants inside the PRCS, informing the entrants of any change in the continuous air monitor, and using the radio for keeping the entry supervisor informed or for calling for rescue. The entry supervisor should review the Permit and procedures to be used in the PRCS with the entrant(s) and attendant. The entry supervisor will sign the permit and contact the manager for authorization to enter the PRCS. The manager will sign and enter the date and time on the Permit.

During the work, the entry supervisor will ensure the Permit is readily available at the PRCS. After the work is done or the Permit is no longer valid, it is returned to the Facilities office or TC.

EMERGENCY PROCEDURES

In the event of a PRCS emergency, the attendant shall contact the entry supervisor and request assistance. The attendant shall attempt non-entry rescue utilizing the retrieval system. The attendant shall not try to enter a PRCS to assist a downed worker. If other workers are in the area of the PRCS, their assistance should be requested. If the entrant is not able to leave the PRCS and a qualified rescue vendor is not present to perform an entry rescue, the entry supervisor shall call 911 and inform the operator that a confined space rescue is required. The entry supervisor shall then contact NYULH Telecommunications (212.263.911). Responding NYULH employees should assist in non-entry rescue, but should not attempt to enter the PRCS.

POST PRCS ENTRY PROCEDURES

After the PRCS entry work is completed, the space should be returned to its original condition in accordance with Facilities' or the building manager's procedures. All lines should be reconnected, unblanked, or unplugged. The Facilities' manager, TC or controlling contractor's competent person should check and authorize the PRCS to be put back into service.

All personal protective and safety equipment that was used in the PRCS entry should be cleaned and returned to storage for future use. If disposable personal protective equipment was used and contaminated with chemicals, it should be placed in a container and given to EH&S for proper disposal (as per Safety Policy No. 108a, Hazardous Waste from Contractors (Construction and Building Maintenance).

If necessary, showers should be provided for workers after the PRCS entry operation is completed.

Building Type of Space Location 222 E. 41 St. Fuel oil tanks 001 and 003 B-040 660 First Ave. Domestic water tank Roof Fuel oil tank Cellar Crawl Space 3 rd floor Radiology Computer Storage Room (above Cytology Lab) 673 First Ave. Fuel oil tank FOT-1 Parking garage (CMC and OSC) - - Ambulatory Care Fuel oil tank ACC-01 C-21 Center (ACC) - - Coles Acid neutralizing tanks G100 Energy Boiler 1 Entrance - 4 th floor North mud drum (two hatches) - 4M Wind box - 4 th floor North steam drum (two hatches) - 4M Wind box - 4 th floor Boiler 2 Entrance - 4 th floor Boiler 2 Entrance - 4 th floor Sump pits (3) Ground Exhaust system Access hatch for exhaust breach, Boiler 1 - 4 th floor Kind Gas turbine cass tack 1 - 4 th floor - 4 th floor Roor Sump pits (3) Ground Exhaust system Access hatch for exhaust breach, Boiler 2		Main Campus and Im	mediate Vicinity
$ \begin{array}{c c c c c c c c c c c c c c c c c c c $	Building		
Fuel oil tank Cellar Cravl Space 3 rd floor Radiology Computer Storage Room (above Cytology Lab) 673 First Ave. (CMC and OSC) Fuel oil tank FOT-1 Parking garage Ambulatory Care Center (ACC) Fuel oil tank ACC-01 C-21 Center (ACC) Domestic water tank Roof Clinical Cancer Domestic water tank Roof Center Fuel oil tank LL-213 Coles Acid neutralizing tanks G100 Energy Boiler 1 Entrance - 4 th floor Fan - 4 th floor North mud drum (two hatches) - 4M Wind box - 4 th floor Boiler 2 Entrance - 4 th floor Boiler 2 Entrance - 4 th floor South mud drum (two hatches) - 4M Wind box - 4 th floor South steam drum (two hatches) - 4M Wind box - 4 th floor South mud drum (two hatches) - 4M Wind box - 4 th floor Sump pits (3) Ground Exhaust system Access hatch for exhaust breach, Boiler 1 - 4 th floor Mica exhaust stack 1 - 4 th floor Roof exhaust stack 2 - 4 th floor Exhaust system Access hatch for exhaust breach, Boiler 2 - 4	222 E. 41 St.	Fuel oil tanks 001 and 003	B-040
Crawl Space 3rd floor Radiology Computer Storage Room (above Cytology Lab) 673 First Ave. (CMC and OSC) Fuel oil tank FOT-1 Parking garage Ambulatory Care Center (ACC) Fuel oil tank ACC-01 C-21 Clinical Cancer Domestic water tank Roof Center Fuel oil tank LL-213 Coles Acid neutralizing tanks G100 Energy Boiler 1 Entrance - 4 th floor North mud drum (two hatches) - 4 th floor North steam drum (two hatches) - 4 th floor Boiler 2 Entrance - 4 th floor South steam drum (two hatches) - 4 th floor South steam drum (two hatches) - 4 th floor South steam drum (two hatches) - 4 th floor Boiler 2 Entrance - 4 th floor Fan - 4 th floor Sump pits (3) Ground Exhaust system Access hatch for exhaust breach, Boiler 1 - 4 th floor Sump pits (3) Ground Exhaust system Access hatch for exhaust breach, Boiler 2 - 4 th floor Exhaust system Access hatch for exhaust breach, Boiler 2 - 4 th floor Exhaust stack 1 - 4 th floor HRSG exhaust Stack 2 - 4 th floor Co eatalyst chamber - 4 th floor Co catalyst chamber - 4 th floor Co catalyst chamber - 4 th floor Mud drum w	660 First Ave.	Domestic water tank	Roof
673 First Ave. (CMC and OSC) Fuel oil tank FOT-1 Parking garage Ambulatory Care Center (ACC) Fuel oil tank ACC-01 C-21 Clinical Cancer Domestic water tank Roof Center (ACC) Domestic water tank Roof Center Fuel oil tank LL-213 Coles Acid neutralizing tanks G100 Energy Boiler 1 Entrance - 4 th floor North mud drum (two hatches) - 4 th floor Boiler 2 Entrance - 4 th floor Boiler 2 Entrance - 4 th floor Boiler 2 Entrance - 4 th floor Boiler 3 Ground Exhaust system Access hatch for exhaust breach, Boiler 1 - 4 th floor Sump pits (3) Ground Exhaust system Access hatch for exhaust breach, Boiler 2 - 4 th floor Exhaust system Access hatch for exhaust breach, Boiler 2 - 4 th floor Exhaust system Access hatch for exhaust breach, Boiler 2 - 4 th floor Exhaust system Access hatch for exhaust breach, Boiler 2 - 4 th floor Exhaust system Access hatch for exhaust breach, Boiler 2 - 4 th floor Roof exhaust duct for gas turbine/boilers - 4M Gas turbine exhaust (two hatches) - 4 th floor <		Fuel oil tank	Cellar
673 First Ave. (CMC and OSC) Fuel oil tank FOT-1 Parking garage Ambulatory Care Center (ACC) Fuel oil tank ACC-01 C-21 Clinical Cancer Domestic water tank Roof Center (ACC) Domestic water tank Roof Center Fuel oil tank LL-213 Coles Acid neutralizing tanks G100 Energy Boiler 1 Entrance - 4 th floor North mud drum (two hatches) - 4 th floor Boiler 2 Entrance - 4 th floor Boiler 2 Entrance - 4 th floor Boiler 2 Entrance - 4 th floor Boiler 3 Ground Exhaust system Access hatch for exhaust breach, Boiler 1 - 4 th floor Sump pits (3) Ground Exhaust system Access hatch for exhaust breach, Boiler 2 - 4 th floor Exhaust system Access hatch for exhaust breach, Boiler 2 - 4 th floor Exhaust system Access hatch for exhaust breach, Boiler 2 - 4 th floor Exhaust system Access hatch for exhaust breach, Boiler 2 - 4 th floor Exhaust system Access hatch for exhaust breach, Boiler 2 - 4 th floor Roof exhaust duct for gas turbine/boilers - 4M Gas turbine exhaust (two hatches) - 4 th floor <		Crawl Space	3 rd floor Radiology Computer Storage Room
673 First Ave. (CMC and OSC) Fuel oil tank FOT-1 Parking garage Ambulatory Care Center (ACC) Fuel oil tank ACC-01 C-21 Clinical Cancer Domestic water tank Roof Center (ACC) Boiler 1 Entrance - 4 th floor Fuel oil tank LL-213 Coles Energy Boiler 1 Entrance - 4 th floor North mud drum (two hatches) - 4 th floor North mud drum (two hatches) - 4 th floor Boiler 2 Entrance - 4 th floor Boiler 2 Entrance - 4 th floor South mud drum (two hatches) - 4 th floor South steam drum (two hatches) - 4 th floor South steam drum (two hatches) - 4 th floor South steam drum (two hatches) - 4 th floor South steam drum (two hatches) - 4 th floor South steam drum (two hatches) - 4 th floor South steam drum (two hatches) - 4 th floor South steam drum (two hatches) - 4 th floor Exhaust system Access hatch for exhaust breach, Boiler 1 - 4 th floor Roof exhaust duct for gas turbine/boilers - 4 th floor Roof exhaust duct for gas turbine/boilers - 4 th floor Roof exhaust access hatch - 5/Roof Fuel oil tank Ground		1	
Center (AĆC) Domestic water tank Roof Clinical Cancer Fuel oil tank LL-213 Coles Acid neutralizing tanks G100 Energy Boiler 1 Entrance - 4 th floor Fan - 4 th floor North mud drum (two hatches) - 4 th floor North steam drum (two hatches) - 4 th floor Boiler 2 Entrance - 4 th floor Fan - 4 th floor Boiler 2 Entrance - 4 th floor Fan - 4 th floor Boiler 3 Ground Boiler 4 Exhaust system Boiler 5 South mud drum (two hatches) - 4 th floor South steam drum (two hatches) - 4 th floor Sump pits (3) Ground Exhaust system Access hatch for exhaust breach, Boiler 1 - 4 th floor Access hatch for exhaust breach, Boiler 2 - 4 th floor Sump pits (3) Ground Exhaust system Access hatch for exhaust breach, Boiler 2 - 4 th floor HRSG exhaust Stack 1 - 4 th floor HRSG exhaust stack 2 - 4 th floor HRSG exhaust stack 2 - 4 th floor HRSG exhaust stack 2 - 4 th floor Generator (HRSG) Fuel oil tank Ground Heat Recovery Steam Generator (HRSG) Ammonia injection chamber - 4 th floor Mud drum west (two hatches) - 4 th floor Steam drum - 4M		Fuel oil tank FOT-1	
Center Fuel oil tank LL-213 Coles Acid neutralizing tanks G100 Energy Boiler 1 Entrance - 4 th floor Fan - 4 th floor North mud drum (two hatches) - 4 th floor North steam drum (two hatches) - 4M Boiler 2 Entrance - 4 th floor South mud drum (two hatches) - 4M Wind box - 4 th floor Boiler 2 Boiler 2 Entrance - 4 th floor Fan - 4 th floor Sump pits (3) Ground Exhaust system Access hatch for exhaust breach, Boiler 1 - 4 th floor Access hatch for exhaust breach, Boiler 2- 4 th floor Exhaust system Access hatch for exhaust breach, Boiler 2- 4 th floor HRSG exhaust Stack 1 - 4 th floor HRSG exhaust Stack 2 - 4 th floor Heat Recovery Steam Generator (HRSG) Fuel oil tank Ground Heat Recovery Steam Generator (HRSG) Ath floor Center (two hatches) - 4 th floor Mud drum wast (two hatches) - 4 th floor	2	Fuel oil tank ACC-01	C-21
$ \begin{array}{ c c c c c c } \hline Coles & Acid neutralizing tanks & G100 \\ \hline Energy & Boiler 1 & Entrance - 4^{th} floor \\ Fan - 4^{th} floor \\ North mud drum (two hatches) - 4^{th} floor \\ North mud drum (two hatches) - 4^{th} floor \\ North steam drum (two hatches) - 4^{th} floor \\ North steam drum (two hatches) - 4^{th} floor \\ \hline Boiler 2 & Entrance - 4^{th} floor \\ Fan - 4^{th} floor \\ South mud drum (two hatches) - 4^{th} floor \\ South mud drum (two hatches) - 4^{th} floor \\ South steam drum (two hatches) - 4^{th} floor \\ South steam drum (two hatches) - 4^{th} floor \\ \hline South steam drum (two hatches) - 4^{th} floor \\ \hline Sump pits (3) & Ground \\ \hline Exhaust system & Access hatch for exhaust breach, Boiler 1 - 4^{th} floor \\ Access hatch for exhaust breach, Boiler 2- 4^{th} floor \\ \hline Access hatch for exhaust breach, Boiler 2- 4^{th} floor \\ \hline Roor \\ Exhaust duct for gas turbine/boilers - 4M \\ Gas turbine exhaust (two hatches) - 4^{th} floor \\ HRSG exhaust Stack 1 - 4^{th} floor \\ HRSG exhaust Stack 2 - 4^{th} floor \\ Roof exhaust access hatch - 5/Roof \\ \hline Fuel oil tank & Ground \\ \hline Heat Recovery Steam \\ Generator (HRSG) & Center (two hatches) - 4^{th} floor \\ CO catalyst chamber - 4^{th} floor \\ Mud drum east (two hatches) - 4^{th} floor \\ Mud drum east (two hatches) - 4^{th} floor \\ Mud drum east (two hatches) - 4^{th} floor \\ Mud drum east (two hatches) - 4^{th} floor \\ Mud drum east (two hatches) - 4^{th} floor \\ Mud drum east (two hatches) - 4^{th} floor \\ Mud drum east (two hatches) - 4^{th} floor \\ Mud drum east (two hatches) - 4^{th} floor \\ Mud drum east (two hatches) - 4^{th} floor \\ Mud drum east (two hatches) - 4^{th} floor \\ Mud drum east (two hatches) - 4^{th} floor \\ Mud drum east (two hatches) - 4^{th} floor \\ Mud drum east (two hatches) - 4^{th} floor \\ Mud drum east (two hatches) - 4^{th} floor \\ Mud drum east (two hatches) - 4^{th} floor \\ Mud crum east (two hatches) - 4^{th} floor \\ Mud crum east (two hatches) - 4^{th} floor \\ Mud crum east (two hatches) - 4^{th} floor \\ Mud crum east (two hatches) - 4^{$	Clinical Cancer	Domestic water tank	Roof
Energy Boiler 1 Entrance - 4 th floor Fan - 4 th floor North mud drum (two hatches) - 4 th floor North steam drum (two hatches) - 4 th floor South steam drum (two hatches) - 4 th floor Fan - 4 th floor South mud drum (two hatches) - 4 th floor South steam drum (two hatches) - 4 th floor Access hatch for exhaust breach, Boiler 1 - 4 th floor Exhaust system Exhaust system Access hatch for exhaust breach, Boiler 2- 4 th floor Exhaust duct for gas turbine/boilers - 4M Gas turbine exhaust (two hatches) - 4 th floor HRSG exhaust Stack 1 - 4 th floor HRSG exhaust Stack 2 - 4 th floor Roof exhaust stack 2 - 4 th floor HRSG exhaust stack 2 - 4 th floor Co extalyst chamber - 4 th floor CO catalyst chamber - 4 th floor CO catalyst chamber - 4 th floor Mud drum west (two hatches) - 4 th floor Mud drum wes	Center	Fuel oil tank	LL-213
Energy Boiler 1 Entrance - 4 th floor Fan - 4 th floor North mud drum (two hatches) - 4 th floor North steam drum (two hatches) - 4 th floor South steam drum (two hatches) - 4 th floor Fan - 4 th floor South mud drum (two hatches) - 4 th floor South steam drum (two hatches) - 4 th floor Access hatch for exhaust breach, Boiler 1 - 4 th floor Access hatch for exhaust breach, Boiler 2- 4 th floor Exhaust duct for gas turbine/boilers - 4M Gas turbine exhaust (two hatches) - 4 th floor HRSG exhaust Stack 1 - 4 th floor HRSG exhaust Stack 2 - 4 th floor HRSG exhaust stack 2 - 4 th floor Co exhaust access hatch - 5/Roof Fuel oil tank Ground Heat Recovery Steam Generator (HRSG) Ammonia injection chamber - 4 th floor CO catalyst chamber - 4 th floor Mud drum west (two hatches) - 4 th floor Mud drum w	Coles		G100
$ \begin{array}{c} Fan - 4^{th} \ floor \\ North mud drum (two hatches) - 4^{th} \ floor \\ North steam drum (two hatches) - 4M \\ Wind box - 4^{th} \ floor \\ Fan - 4^{th} \ floor \\ Fan - 4^{th} \ floor \\ South mud drum (two hatches) - 4M \\ Wind box - 4^{th} \ floor \\ South mud drum (two hatches) - 4M \\ Wind box - 4^{th} \ floor \\ South mud drum (two hatches) - 4M \\ Wind box - 4^{th} \ floor \\ South steam drum (two hatches) - 4M \\ Wind box - 4^{th} \ floor \\ South steam drum (two hatches) - 4M \\ Wind box - 4^{th} \ floor \\ South steam drum (two hatches) - 4M \\ Wind box - 4^{th} \ floor \\ Sump pits (3) \\ Exhaust system \\ \hline Access hatch for exhaust breach, Boiler 1 - \\ 4^{th} \ floor \\ Access hatch for exhaust breach, Boiler 2 - \\ 4^{th} \ floor \\ Exhaust duct for gas turbine/boilers - 4M \\ Gas turbine exhaust (two hatches) - 4^{th} \ floor \\ HRSG exhaust Stack 1 - 4^{th} \ floor \\ HRSG exhaust Stack 2 - 4^{th} \ floor \\ HRSG exhaust Stack 2 - 4^{th} \ floor \\ Roof exhaust stacks 1 - 5/Roof \\ \hline Fuel oil tank \\ Heat Recovery Steam \\ Generator (HRSG) \\ \hline Heat Recovery Steam \\ Generator (HRSG) \\ \hline Mud drum exet (two hatches) - 4^{th} \ floor \\ Mud drum west (two hatches) - 4^{th} \ floor \\ Mud drum west (two hatches) - 4^{th} \ floor \\ Mud drum west (two hatches) - 4^{th} \ floor \\ Mud drum west (two hatches) - 4^{th} \ floor \\ Mud drum west (two hatches) - 4^{th} \ floor \\ Mud drum west (two hatches) - 4^{th} \ floor \\ Mud drum west (two hatches) - 4^{th} \ floor \\ Mud drum west (two hatches) - 4^{th} \ floor \\ Mud drum west (two hatches) - 4^{th} \ floor \\ Mud drum west (two hatches) - 4^{th} \ floor \\ Mud drum west (two hatches) - 4^{th} \ floor \\ Mud drum west (two hatches) - 4^{th} \ floor \\ Mud drum west (two hatches) - 4^{th} \ floor \\ Mud drum west (two hatches) - 4^{th} \ floor \\ Mud drum west (two hatches) - 4^{th} \ floor \\ Mud drum west (two hatches) - 4^{th} \ floor \\ Mud drum west (two hatches) - 4^{th} \ floor \\ Mud drum west (two hatches) - 4^{th} \ floor \\ Mud drum west (two hatches) - 4^{th} \ floor \\ Mud drum w$			Entrance - 4 th floor
North steam drum (two hatches) – 4M Wind box – 4th floorBoiler 2Entrance – 4th floor Fan – 4th floor South mud drum (two hatches) – 4th floor South steam drum (two hatches) – 4th floor South steam drum (two hatches) – 4th floorSump pits (3)GroundExhaust systemAccess hatch for exhaust breach, Boiler 1 – 4th floor Access hatch for exhaust breach, Boiler 2- 4th floor Access hatch for exhaust breach, Boiler 2- 4th floor Bas turbine exhaust (two hatches) – 4th floor HRSG exhaust Stack 1 – 4th floor HRSG exhaust Stack 2 – 4th floor HRSG exhaust Stack 2 – 4th floor Generator (HRSG)Fuel oil tankGroundHeat Recovery Steam Generator (HRSG)Ammonia injection chamber – 4th floor Mud drum east (two hatches) – 4th floor Mud drum west (two hatches) – 4th floor Mud drum	65		Fan – 4 th floor
North steam drum (two hatches) – 4M Wind box – 4th floorBoiler 2Entrance – 4th floor Fan – 4th floor South mud drum (two hatches) – 4th floor South steam drum (two hatches) – 4th floor South steam drum (two hatches) – 4th floorSump pits (3)GroundExhaust systemAccess hatch for exhaust breach, Boiler 1 – 4th floor Access hatch for exhaust breach, Boiler 2- 4th floor Access hatch for exhaust breach, Boiler 2- 4th floor Bas turbine exhaust (two hatches) – 4th floor HRSG exhaust Stack 1 – 4th floor HRSG exhaust Stack 2 – 4th floor HRSG exhaust Stack 2 – 4th floor Generator (HRSG)Fuel oil tankGroundHeat Recovery Steam Generator (HRSG)Ammonia injection chamber – 4th floor Mud drum east (two hatches) – 4th floor Mud drum west (two hatches) – 4th floor Mud drum			North mud drum (two hatches) – 4^{th} floor
Wind box -4^{th} floorBoiler 2Entrance -4^{th} floor Fan -4^{th} floor South mud drum (two hatches) -4^{th} floor South steam drum (two hatches) -4^{th} floor South steam drum (two hatches) -4^{th} floorSump pits (3)GroundExhaust systemAccess hatch for exhaust breach, Boiler 1 $-$ 4^{th} floor Access hatch for exhaust breach, Boiler 2- 4^{th} floor Exhaust duct for gas turbine/boilers -4^{th} floor HRSG exhaust (two hatches) -4^{th} floor HRSG exhaust Stack $1 - 4^{th}$ floor HRSG exhaust Stack $2 - 4^{th}$ floor HRSG exhaust stack $2 - 4^{th}$ floor Generator (HRSG)Fuel oil tankGroundHeat Recovery Steam Generator (HRSG)Armonia injection chamber -4^{th} floor Mud drum west (two hatches) -4^{th} floor Mud drum stank -4^{th} floor by Stair B			
Boiler 2Entrance -4^{th} floor Fan -4^{th} floor South mud drum (two hatches) -4^{th} floor South steam drum (two hatches) -4^{th} floor South steam drum (two hatches) -4^{th} floorSump pits (3)GroundExhaust systemAccess hatch for exhaust breach, Boiler 1 -4^{th} floor Access hatch for exhaust breach, Boiler 2- 4^{th} floor Exhaust duct for gas turbine/boilers -4^{th} floor HRSG exhaust Stack $1 - 4^{th}$ floor HRSG exhaust Stack $2 - 4^{th}$ floor HRSG exhaust access hatch $-5/Roof$ Fuel oil tankGroundHeat Recovery Steam Generator (HRSG)Ammonia injection chamber -4^{th} floor CO catalyst chamber -4^{th} floor Mud drum west (two hatches) -4^{th} floor Mud drum west (two hatc			
Fan -4^{th} floor South mud drum (two hatches) -4^{th} floor South steam drum (two hatches) -4^{th} floor South steam drum (two hatches) -4^{th} floorSump pits (3)GroundExhaust systemAccess hatch for exhaust breach, Boiler $1 - 4^{th}$ floor Access hatch for exhaust breach, Boiler $2 - 4^{th}$ floor Exhaust duct for gas turbine/boilers -4^{th} floor Exhaust duct for gas turbine/boilers -4^{th} floor HRSG exhaust Stack $1 - 4^{th}$ floor HRSG exhaust Stack $2 - 4^{th}$ floor Generator (HRSG)Fuel oil tankGroundHeat Recovery Steam Generator (HRSG)Ammonia injection chamber -4^{th} floor CO catalyst chamber -4^{th} floor Mud drum east (two hatches) -4^{th} floor Mud drum west (two hatches) -4^{th} floor Mud drum west (two hatches) -4^{th} floor Mud drum west (two hatches) -4^{th} floor Steam drum $-4M$ MiscellaneousAmmonia tank - 4th floor by Stair B		Boiler 2	Entrance – 4 th floor
South steam drum (two hatches) – 4M Wind box – 4th floorSump pits (3)GroundExhaust systemAccess hatch for exhaust breach, Boiler 1 – 4th floor Access hatch for exhaust breach, Boiler 2- 4th floor Exhaust duct for gas turbine/boilers – 4M Gas turbine exhaust (two hatches) – 4th floor HRSG exhaust Stack 1 – 4th floor HRSG exhaust Stack 2 – 4th floor Roof exhaust access hatch – 5/RoofFuel oil tankGroundHeat Recovery Steam Generator (HRSG)Ammonia injection chamber – 4th floor CO catalyst chamber – 4th floor Mud drum west (two hatches) – 4th floor Steam drum – 4MMiscellaneousAmmonia tank - 4th floor by Stair B			
South steam drum (two hatches) – 4M Wind box – 4th floorSump pits (3)GroundExhaust systemAccess hatch for exhaust breach, Boiler 1 – 4th floor Access hatch for exhaust breach, Boiler 2- 4th floor Exhaust duct for gas turbine/boilers – 4M Gas turbine exhaust (two hatches) – 4th floor HRSG exhaust Stack 1 – 4th floor HRSG exhaust Stack 2 – 4th floor Roof exhaust access hatch – 5/RoofFuel oil tankGroundHeat Recovery Steam Generator (HRSG)Ammonia injection chamber – 4th floor CO catalyst chamber – 4th floor Mud drum west (two hatches) – 4th floor Steam drum – 4MMiscellaneousAmmonia tank - 4th floor by Stair B			South mud drum (two hatches) – 4^{th} floor
Wind box - 4th floorSump pits (3)GroundExhaust systemAccess hatch for exhaust breach, Boiler 1 - 4th floor Access hatch for exhaust breach, Boiler 2- 4th floor Exhaust duct for gas turbine/boilers - 4M Gas turbine exhaust (two hatches) - 4th floor HRSG exhaust Stack 1 - 4th floor HRSG exhaust Stack 2 - 4th floor Roof exhaust access hatch - 5/RoofFuel oil tankGroundHeat Recovery Steam Generator (HRSG)Ammonia injection chamber - 4th floor CO catalyst chamber - 4th floor Mud drum east (two hatches) - 4th floor Steam drum - 4MMiscellaneousAmmonia tank - 4th floor by Stair B			
Exhaust systemAccess hatch for exhaust breach, Boiler 1 – 4th floor Access hatch for exhaust breach, Boiler 2- 4th floor Exhaust duct for gas turbine/boilers – 4M Gas turbine exhaust (two hatches) – 4th floor HRSG exhaust Stack 1 – 4th floor HRSG exhaust Stack 2 – 4th floor Roof exhaust access hatch – 5/RoofFuel oil tankGroundHeat Recovery Steam Generator (HRSG)Ammonia injection chamber – 4th floor CO catalyst chamber – 4th floor Mud drum east (two hatches) – 4th floor Steam drum – 4MMiscellaneousAmmonia tank - 4th floor by Stair B			
Exhaust systemAccess hatch for exhaust breach, Boiler 1 – 4th floor Access hatch for exhaust breach, Boiler 2- 4th floor Exhaust duct for gas turbine/boilers – 4M Gas turbine exhaust (two hatches) – 4th floor HRSG exhaust Stack 1 – 4th floor HRSG exhaust Stack 2 – 4th floor Roof exhaust access hatch – 5/RoofFuel oil tankGroundHeat Recovery Steam Generator (HRSG)Ammonia injection chamber – 4th floor Co catalyst chamber – 4th floor Mud drum east (two hatches) – 4th floor Steam drum – 4MMiscellaneousAmmonia tank - 4th floor by Stair B		Sump pits (3)	Ground
4th floorExhaust duct for gas turbine/boilers – 4MGas turbine exhaust (two hatches) – 4th floorHRSG exhaust Stack 1 – 4th floorHRSG exhaust Stack 2 – 4th floorHRSG exhaust Stack 2 – 4th floorRoof exhaust access hatch – 5/RoofFuel oil tankGenerator (HRSG)Ammonia injection chamber – 4th floorCo catalyst chamber – 4th floorCo catalyst chamber – 4th floorMud drum east (two hatches) – 4th floorMud drum west (two hatches) – 4th floorSteam drum – 4MMiscellaneousAmmonia tank - 4th floor by Stair B			
Gas turbine exhaust (two hatches) - 4th floor HRSG exhaust Stack 1 - 4th floor HRSG exhaust Stack 2 - 4th floor Roof exhaust access hatch - 5/RoofFuel oil tankGroundHeat Recovery Steam Generator (HRSG)Ammonia injection chamber - 4th floor Center (two hatches) - 4th floor CO catalyst chamber - 4th floor Mud drum east (two hatches) - 4th floor Mud drum west (two hatches) - 4th floor Mud drum at the floor by Stair B			· · · · · · · · · · · · · · · · · · ·
Gas turbine exhaust (two hatches) - 4th floor HRSG exhaust Stack 1 - 4th floor HRSG exhaust Stack 2 - 4th floor Roof exhaust access hatch - 5/RoofFuel oil tankGroundHeat Recovery Steam Generator (HRSG)Ammonia injection chamber - 4th floor Center (two hatches) - 4th floor CO catalyst chamber - 4th floor Mud drum east (two hatches) - 4th floor Mud drum west (two hatches) - 4th floor Mud drum at the floor by Stair B			Exhaust duct for gas turbine/boilers – 4M
HRSG exhaust Stack 1 – 4th floor HRSG exhaust Stack 2 – 4th floor Roof exhaust access hatch – 5/RoofFuel oil tankGroundHeat Recovery Steam Generator (HRSG)Ammonia injection chamber – 4th floor Co catalyst chamber – 4th floor CO catalyst chamber – 4th floor Mud drum east (two hatches) – 4th floor Mud drum west (two hatches) – 4th floor Steam drum – 4MMiscellaneousAmmonia tank - 4th floor by Stair B			
Fuel oil tankGroundHeat Recovery SteamAmmonia injection chamber – 4th floorGenerator (HRSG)Center (two hatches) – 4th floorCO catalyst chamber – 4th floorMud drum east (two hatches) – 4th floorMud drum west (two hatches) – 4th floorMiscellaneousAmmonia tank - 4th floor by Stair B			
Fuel oil tankGroundHeat Recovery Steam Generator (HRSG)Ammonia injection chamber - 4th floor Center (two hatches) - 4th floor CO catalyst chamber - 4th floor Mud drum east (two hatches) - 4th floor Mud drum west (two hatches) - 4th floor Mud drum west (two hatches) - 4th floor Steam drum - 4MMiscellaneousAmmonia tank - 4th floor by Stair B			HRSG exhaust Stack 2 – 4 th floor
Heat Recovery Steam Generator (HRSG)Ammonia injection chamber - 4th floor Center (two hatches) - 4th floor CO catalyst chamber - 4th floor Mud drum east (two hatches) - 4th floor Mud drum west (two hatches) - 4th floor Steam drum - 4MMiscellaneousAmmonia tank - 4th floor by Stair B			
Generator (HRSG)Center (two hatches) – 4th floor CO catalyst chamber – 4th floor Mud drum east (two hatches) – 4th floor Mud drum west (two hatches) – 4th floor Steam drum – 4MMiscellaneousAmmonia tank - 4th floor by Stair B		Fuel oil tank	Ground
Generator (HRSG)Center (two hatches) – 4th floor CO catalyst chamber – 4th floor Mud drum east (two hatches) – 4th floor Mud drum west (two hatches) – 4th floor Steam drum – 4MMiscellaneousAmmonia tank - 4th floor by Stair B		Heat Recovery Steam	Ammonia injection chamber – 4 th floor
CO catalyst chamber – 4th floor Mud drum east (two hatches) – 4th floor Mud drum west (two hatches) – 4th floor Steam drum – 4MMiscellaneousAmmonia tank - 4th floor by Stair B			
Mud drum east (two hatches) – 4th floor Mud drum west (two hatches) – 4th floor Steam drum – 4MMiscellaneousAmmonia tank - 4th floor by Stair B		× ,	
Mud drum west (two hatches) – 4th floor Steam drum – 4MMiscellaneousAmmonia tank - 4th floor by Stair B			
Steam drum – 4MMiscellaneousAmmonia tank - 4th floor by Stair B			
Miscellaneous Ammonia tank - 4th floor by Stair B			
		Miscellaneous	Ammonia tank - 4th floor by Stair B
Blow down tank $-4^{\text{\tiny H}}$ theor			Blow down tank -4^{th} floor

List of Permit-required Confined Spaces in Facilities Owned by NYULH

		a 1 1 1 that
		Condensate polisher, east -4^{th} floor
		Condensate polisher, west -4^{th} floor
		Condensate receiver -4^{th} floor
		De-aerator – 4M
		Hatch on exhaust breach for gas turbine –
		4M
		Water storage feed tank – 4M
Greenberg Hall (GBH)	Sump pits > 4 feet deep (2)	SC2 Mechanical Room
Kimmel Pavilion	CoGen flue	6 hatches on the 6 th floor
KIIIIIICI I aviitoli	Cooch nuc	1 hatch on 19 th floor
	Domestic water tank	20 th floor
	Ejector pits (4)	Ground floor, Room 706B and 850D
	Elevator pits	Ground floor
	Flood barrier catch basins (5)	Outside, 1 st Ave. side of bldg.
	AST fuel oil tank (3 hatches)	Ground floor, Room 706
	Storm Water Retention Tank	Outside, 1 st Ave. side of building.
	Sump pits > 4 feet deep	C-044 and C-070
Medical Science	Acid neutralizing tanks	MS 191
Building (MSB)	Domestic water tanks (2)	10 th floor
	Sump pits > 4 feet deep	C-06, C-031A, and C-068
Science Building	Acid neutralization tank	C-12
	Crawl Space	G-06 inside Conference Room Closet
	Domestic water tanks (2)	Roof
	Sump pits > 4 feet deep	C-03 and C-13
	Elevator pits	Ground floor
	Flood barrier catch basin (1)	30 th Street
	Fuel tank (2 hatches)	C-04
	Gasket space between Science	220 (fire pump MER)
	and MSB	
	Storm water retention tank	C-05
Schwartz Lecture Hall	Sump pits > 4 feet deep	Cellar MER next to elevator machine room
Skirball	Acid neutralizing tanks (2)	1^{st} floor – north and south (outside by flag
SKIIUAII	Acid fieutralizing talks (2)	
	$\mathbf{D}_{\mathbf{r}}$	pole 25 th floor
	Domestic water tanks (2)	
	Fuel oil tanks (2)	Skirball Ground Animal Facility Oil Tank
	HCC-01	Room, west
	SK-01	Oil Tank Room, east
	Reverse osmosis tank	6 th floor MER
	Sump pits > 4 feet deep (10)	Ground floor - Steam Room (3)
		Ground floor - Outside Gas P.O.E. Room (2)
		Ground floor – Sump Pump Room in AF (3)
		Ground floor – MER (2)
Smilow	Acid neutralizing tank	Sump Room C-27 (in morgue)

	Fuel oil tanks	SM01D: 1 st floor - 105A
		SM01M: Mezzanine - MZ-08
	Sumps pits $>$ 4 feet deep (3)	C-39 and C-17 (in morgue)
Tisch	Domestic water tank (2)	20 th floor
	Utility shaft	Ground floor, adjacent service elevators
	Sump pits > 4 feet deep	C 21A, C 56, and C-160
Translational	Fuel oil tank TRB-01	Basement MER
Research Building		

List of Permit-required Confined Spaces in Facilities Owned by NYULH

NYU Langone Orthopedic Hospital				
Type of Space	Location			
Domestic water tanks	C1, C-119 (cold water)			
	C1, C-119 (hot water)			
Ejector pits > 4 feet deep	SC3, C-304 (men's locker room)			
	SC3, C-316, (maintenance shop)			
Fuel oil tankSC3, by passenger elevators				
Storm pit	SC3, C-304 (men's locker room)			
	SC3, C-316, (maintenance shop)			

NYU Langone Hospital - Brooklyn					
Type of Space	Location				
Boilers (3)	Room 1181				
Domestic water tank	7 th floor roof				
Elevator pits	1 st floor				
Sump pits > 4 feet deep	1 st floor Switch Gear Room (inside Electrical Room)				
	1 st floor LB 1523				
Air handler MER	1 st floor Stair H				

NYU Langone Hospital - Long Island Main Campus					
Type of Space	Location				
Boilers (3)	Laundry Building				
Deaerator tank (2)	Laundry Building				
Elevator pits	Lower Level				
Sump pits > 4 feet deep	MER's 2, 4, 10, 11 & 35				
Fuel Oil Tanks	Tank #'s 5816, 0070, 5817 & 0009				
Boiler Stack	Laundry Building				

NYU Langone Hospital - Long Island Research Building	
Type of Space	Location
Sump Pit	Underground Garage

List of Permit-required Confined Spaces in Facilities Owned by NYULH

NYU Langone Hospital - Long Island 120 Mineola Blvd		
Type of Space	Location	
Pit for chiller	Back driveway	
Chillers	Rooftop	

Sterling Forest (formerly NIEM)		
Type of Space	Location	
Fuel storage tanks (2)	Outdoors, underground	